

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located in:

Corner Code ≠

- | | | |
|------------------------------------|---------------------------|--------------------|
| 1. Public Land Survey | T <u>34N</u> R <u>26W</u> | <u>G-11, E-13.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on 10/17, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-11. NE section corner of Section 33. Wood post, James Mullet, D.S. - 1848.
 Beech 10, N56E, 18 lks. Hemlock 18, S41W, 30 lks.
 Set 4" cedar post from Gov't. B.T. - CO Surveyor Haas dated May 27, 1900.
- E-13. SW section corner of Section 33. Wood post. John Mullet, D.S.
 Tam. 12 - N46W, 14 lks.
 Tam. 12 - N49E, 19 lks.
 Tam. 12 - S28E, 25 lks.
 Cedar 10 - S82W, 10 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-11. Mea. south from the E 1/4 and east from the S 1/4 corner of Section 28 according to the record of Co. Surveyor Haas. From this point found rotted remains of hemlock near proper position for SW OBT and mound of earth caused by blow down tree near proper position for NE OBT - scalped off leaf mold and surface of ground and found discolored soil and rotted wood in shape of a stake upright and coming to a point on the bottom end. I believe this is the remains of the cedar post set by Surveyor Haas and I set a DNR monument in the old rotted post bottom. Measurements north and west don't match Surveyor Haas record exactly but are very close. An old blaze line runs east from this monument as set.
- E-13. Found point of two old cedar posts side by side in old E-W swamp road. Remains of all three tam. OBT's are in place. The Cedar would fall in the swamp road. The NW tam. is a 20" stump in poor condition but showing many old axe marks. The NE tam. is a stump showing one axe mark

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|--------------------------|-----------------------|---|
| G-11. DNR Monument. | E-13. DNR Monument | and a large callous overgrowth now detached from the stump. The SE tam. is a large, rotted stump. |
| 6" hemlock, S73W, 63.9' | 4" cedar, N63E, 22.0' | |
| 6" hemlock, N52W, 35.2' | 9" cedar, S62E, 15.9' | |
| 8" hemlock, N62E, 33.1' | 5" cedar, S38W, 17.4' | |
| 8" y.birch, S34E, 23.55' | 6" cedar, N13W, 10.8' | |

Signed by David B. Babbitt

Date 12-28-89

Surveyor's Michigan License No. 21558