

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located In:

Corner Code ~~##~~

- | | | |
|---------------------------------------|---------------------------|-----------------|
| 1. Public Land Survey | T <u>34N</u> R <u>26W</u> | <u>6, 2, 5.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling
in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David B. Babbitt, in a field survey on 1/30/90, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

6. Northeast 1/16 corner of Section 35. No previous record.
2. East 1/16 corner on the north section line of Section 35. No previous record.
5. North 1/16 corner of Section 35. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

6. Corner set at center of northeast 1/4 of Section 35 by closed traverse.
2. Corner set MPOL between northeast corner and north 1/4 corner of Section 35.
5. Corner set MPOL between north 1/4 corner and computed center corner of Section 35 by closed traverse.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---------------------------|-------------------------------|---------------------------|
| 6. DNR Monument | 2. DNR Monument | 5. DNR Monument |
| 12" hemlock, N36E, 34.4' | 9" cedar, N4E, 14.85' | 12" hemlock, N35E, 37.35' |
| 12" hemlock, S44E, 66.75' | 7" cedar, S21E, 10.15' | 5" cedar, S44E, 13.9' |
| 5" red maple, S36W, 13.4' | 8" yellow birch, S63W, 19.45' | 7" red maple, S54W, 22.2' |
| 17" hemlock, N45W, 8.15' | 8" cedar, N64W, 41.95' | 7" cedar, N11W |

Signed by David B. Babbitt

Date 2-21-90

Surveyor's Michigan License No. 21558