

REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 Co. 12/12 199 2
Mc Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>34</u> N R <u>26</u> W	M-03
	T <u>34</u> N R <u>26</u> W	<u>A-03</u> ✓
	T <u>34</u> N R <u>26</u> W	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	

REGISTERED FOR RECORD

97 DEC 22 AM 11:28

PAGE # 604, BK 5

REGISTERED FOR RECORD

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
(SAME AS CORNER A-03 T34N-R26W)

I, William Lenca, in a field survey on July 31, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1847: Original Survey -Township Boundary by H. Floyd - B.T.'s - Cedar, 10" - N20°W - 19 lks.; Elm, 18" - S40°W - 24 lks. All original evidence for this corner has been destroyed by county road improvements.
 - 1848: Original Survey - Sectional Subdivision by James H. Mullett - B.T.'s - B. Ash, 14" - N20°E - 13 lks.; Birch, 16" - S58°E - 29 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
We found a railroad spike in the centerline of county roads East - West and South. This position has been used by local surveyors for several years, matches well with existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N05°E	28.25 feet	
6" dia. White Ash	S30°E	81.72 feet	Scr. NBT
4" dia. Double Maple	S69°W	82.17 feet	Scr. NBT
4" dia. White Ash	N64°W	75.74 feet	Scr. NBT
Metal Survey Sign Post	N05°E	29.4 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 09, 1997
Surveyor's Michigan License No. 26461



604