

# SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/10 1997  
McDermott RLS  
Chairman

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MENOMINEE  
(County)

Located In: Corner Code #

1. Public Land Survey

T34N R 27W

M-05

T34R26

A-05

2. Property Controlling  
in Section

S    T    R   

3. Miscellaneous  
Property in Sec.

S    T    R   

RECEIVED FOR RECORD  
 97 DEC 22 AM 11:29  
 REGISTER OF DEEDS  
 606 BKS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SAME AS CORNER A-5, T34N-R26W

I, William Lenca, in a field survey on July 02, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey - Township Boundary by H. Floyd - B.T.'s - Sugar, 14" - N30°W - 34 lks.; Hemlock, 12" - S20°W - 30 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1848: Original Survey - Sectional Subdivision by James H. Mullett - B.T.'s - Elm, 12" - N57°E - 53 lks.; Hemlock, 10" - S65°E - 17 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: L.C.R.C. No. 322 by William Lenca states, "Found a large spike in a position indicated by the intersection of county road centerlines north, south, east, and west." Set 1/2" x 18" Iron/Ident. cap R.L.S. 26461. TIES: Tel. Cable Box marked with "+" on top - N40°W - 36.82'; Concrete Project Marker with "+" on top - S41°W - 43.28'; Power Pole with tack in side - S35°E - 44.86'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

We found a 1/2 inch diameter iron in the centerline of a four way county road intersection as indicated in L.C.R.C. No. 322. This corner position fits well with other corners in the area and with long standing lines of occupation, has been used by local surveyors for many years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

28" dia. Maple	N45°E	80.53 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S32°E	45.77 feet	1.0' S. of P.P.
8" dia. Tamarack	S50°W	80.37 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N35°W	37.30 feet	0.7' S. of Fence Cor.
Metal Survey Sign Post	S32°E	46.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 09, 1997