

FEB 11 1998

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 12/18, 1997  
Mr. Davis PLS  
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MENOMINEE

(County)

Located in:

Corner Code #

1. Public Land Survey

T34N R 27W

M-06

T R

T34 R 26

A-06 ✓

T R

2. Property Controlling  
In Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

(SAME AS CORNER A-06, T34N - R26W)

I, William Lenca, in a field survey on Nov. 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

97 DEC 22 PM 11:29  
PAGE # 607, BK 5  
MICHIGAN REGISTER OF DEEDS  
LANSING, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd - B.T.'s - Lynn, 12" - N75°W - 22 lks.; Sugar, 12" - S38°W - 34 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: L.C.R.C. No. 322 by William Lenca states, "Set corner on line and midway between the Northeast Corner and the Southeast Corner of Section 13, T34N - R27W. This position matches with the center of a lane to the east and fits well with the centerline of Range Line Road north and south." Set 1/2" x 18" Iron/Ident. cap marked R.L.S. 26461. TIES: Power Pole (tack in side) - N58°E - 34.78'; Basswood, 12" - N43°W - 82.60'; 1/2" x 18" Iron - West - 33.00'.
- 1989: C.S. No. 625 by William Lenca shows this corner in relation to other corners in Section 13, T34N - R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1/2 inch diameter iron with an identification cap marked R.L.S. 26461 at Midpoint and on line between Section corners as indicated in Land Corner Recordation Certificate number 322. This iron is inside a square monument box which is 0.3' below the road surface. We accepted the existing corner monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3-1/4" dia. Alum. cap stamped for corner location on existing 1/2" iron inside of Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N58°E	35.18 feet	1.0' N.W. of P.P.
8" dia. Cedar	S77°E	60.03 feet	Scr. NBT
4" dia. Twin Maple	S89°W	47.28 feet	Scr. NBT
6" dia. Cedar	N31°W	66.72 feet	Scr. NBT
Metal Survey Sign Post	N86°W	33.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 12, 1997

