

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Feb 11 1998
Mc. Davis
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located in: Corner Code #

- | | | |
|---------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey | T <u>34</u> N R <u>26</u> W | M-08 |
| | T___ R ___ | <u>A-08</u> |
| 2. Property Controlling
in Section | S___ T___ R___ | _____ |
| 3. Miscellaneous
Property in Sec. | S___ T___ R___ | _____ |

REGISTERED TO BE RECORDED
97 FEB 22 AM 11: 29
INDEXED 609, BKS
REGISTERED TO BE RECORDED
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
(SAME AS CORNER A-08, T34N - R26W)


1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William Lenca, in a field survey on July 02, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1847: Original Survey by H. Floyd - B.T.'s - Y. Birch, 6" - N55°W - 22 lks.; Cedar, 8" - S70°W - 21 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No evidence of the original corner accessories, or evidence of a subsequent restoration was found. We therefore set this corner midway between the Northeast and Southeast corners of Section 24, T34N - R27W and in the centerline of a North - South County Road, and accepted this location as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" N50°E 39.55 feet 1.0' S. of P.P.
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" S42°E 44.19 feet 3.0' S.W. of Tel. Box
8" dia. White Ash S47°W 84.88 feet Scr. NBT
4" dia. Double White Ash N39°W 68.00 feet Scr. NBT
Metal Survey Sign Post N50°E 40.5 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 12, 1997
Surveyor's Michigan License No. 26461

609