

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/18 1997
McAnis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T^{34N} R^{27W}

M-10

T R

T³⁴ R²⁶

A-10

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

RECEIVED FOR RECORD
97 DEC 22 AM 11:29
PAGE 6 611 BKS
REGISTERED LAND SURVEYOR
WILLIAM LENCA

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

(SAME AS CORNER A-10 T34N-R26W)

I, William Lenca, in a field survey on Nov. 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd - B.T.'s - Elm, 6" - N85°W - 19 lks.; Elm, 8" - S64°W - 55 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1895: Plat of Survey by Justus Little shows this corner in relation to other corners in Section 30, T34N - R26W. No monument is described and no witnesses are given.
- 1997: Plat of Survey by William Lenca shows this corner as it relates to other corners in Section 25, T34N-R27W, and states that a railroad spike was set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a railroad spike 4.5' West of the centerline of a North - South county road. This corner was established in the centerline of county roads North, South, and East, but new construction has moved the North - South centerline 4.5' to the East. The corner falls in line with the centerline of a county road running East and fits with the 1/16 fence to the North. We accepted this location as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

6" dia. White Ash	N58°E	64.25 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S52°E	44.90 feet	1' S. of Road Sign
9" dia. White Ash	S62°W	52.34 feet	Scr. NBT
7" dia. White Ash	N37°W	59.37 feet	Scr. NBT
Metal Survey Sign Post	West	34.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 12, 1997