

REMONUMENTATION

FEB 11 1998

Approved by Menominee County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On 12/18/97 Chairman Mac Brown RLS

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in MENOMINEE (County)

Table with columns: Located In: (Township/Range), Corner Code # (M-11), and handwritten 'A-11' in a circle.

- 1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.

RECORDED FOR RECORD 97 DEC 22 AM 11:29 PAGE 6-13 BKS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____
(SAME AS CORNER A-11 T34N-R26W)

I, William Lenca, in a field survey on Nov. 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 6-36.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey -Township Boundary - by H. Floyd - B.T.'s - Beech, 9" - S42°W - 25 lks.; Hemlock, 48" - N62°W - 52 lks. All original evidence for this corner has been destroyed by county road improvements.
1848: Original Survey - Sectional Subdivision - by James H. Mullett - B.T.'s - Beech, 10" - N28°E - 33 lks.; Beech, 10" - S35°E - 61 lks. All original evidence for this corner has been destroyed by county road improvements.
1895: Plat of Survey by Justus Little shows this corner in relation to other corners in Section 30, T34N - R26W. No monument is described and no witnesses are given.
1981: Certified Survey No. 215 by William Lenca, RLS 26461, states in the legend that a 3/4" x 18" iron pipe with identification cap was set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

New construction has removed the iron pipe which was set at this location. We re-established the corner by using ties to corners 1/2 mile South and 1/2 mile West. The corner position falls in the centerline of county roads North - South and West, fits well with other corners in the area, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

Table listing monument details: 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" @ Survey Sign Post (East 29.07 feet), 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 1.3' S. of Tel. Box (S35°W 55.10 feet), 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 1.1' S. of Power Pole (N30°W 59.73 feet), Metal Survey Sign Post (East 29.6 feet).

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 12, 1997

612