

# SURVEY & REMONUMENTATION

JAN 09 2001

## SECTION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MENOMINEE

(County)

Located In: Corner Code #

- |                                       |  |       |
|---------------------------------------|--|-------|
| 1. Public Land Survey                 | T <u>35</u> N R <u>26</u> W            | B-13  |
|                                       | T <u>   </u> R <u>   </u>              | _____ |
|                                       | T <u>   </u> R <u>   </u>              | _____ |
|                                       | T <u>   </u> R <u>   </u>              | _____ |
|                                       | T <u>   </u> R <u>   </u>              | _____ |
| 2. Property Controlling<br>in Section | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |
|                                       | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |
| 3. Miscellaneous<br>Property in Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |
|                                       | S <u>   </u> T <u>   </u> R <u>   </u> | _____ |

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. Of 1990 On 12/22, 2000  
McL. Davis PLS  
Chairman

Bk. 6 Pg. 227

RECEIVED FOR RECORD

28 DEC 2000 2:31:31 PM

BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SAME AS CORNER B-1, T34N - R26W

I, William Lenca, in a field survey on Oct., 19   00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 12" - N45°E - 7 lks.; Cedar, 8" - N68°W - 45 lks. All original evidence for this corner has been destroyed by County Road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We set this corner in the centerline of County Roads running East - West and North and in line with an old fence line running South. This position fits well with the single proportional location for this corner and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- |   |       |             |                          |
|---|-------|-------------|--------------------------|
| 11" dia. Elm  | N52°E | 102.93 feet | Scr. NBT                 |
| 9" dia. Elm   | S64°E | 106.63 feet | Scr. NBT                 |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | South | 23.82 feet  | @ Survey Sign Post       |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N43°W | 35.85 feet  | 1.0' S. of Rd. Sign Pole |
| Metal Survey Sign Post  | South | 24.5 feet   |                          |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca 26461  
Surveyor's Michigan License No. \_\_\_\_\_

Date Nov. 17, 2000