

# SURVEY & REMONUMENTATION

JAN 09 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 of  
P.A. Of 1990 On 7/13, 2000  
Mr. David RLS  
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 35NR 26W

G-13

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_

T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_

T \_\_\_ R \_\_\_

S \_\_\_

T \_\_\_ R \_\_\_

Book 6 Page 167

RECEIVED FOR RECORD  
13 DEC 2000 10:16:09 A  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims

SAME AS CORNER G-1, T34N-R26W

I, William Lenca, in a field survey on May, 19 00 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 10" - N45°E - 18 lks.; Cedar, 18" - N40°W - 5 lks. All original evidence for this corner has been destroyed by County Road improvements.
- 1970: L.C.R.C. No. 765, Vol. 2 by Frank Bray states 2-1/2" iron pipe with 2'1/2" brass cap re-witnessed as set by the U.S. General Land Office in 1949. Monument is set at ground level in east wheel track of dirt road. TIES: 6" Cedar - S30°W - 24.9'; 13" Cedar - S46°E - 31.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 2-1/2 inch diameter iron pipe with 2-1/2 inch diameter brass cap in the East wheel track of a dirt road, and 2 Cedar B.T.'s as described in L.C.R.C. No. 765 (see part A). This corner has been accepted and used by local surveyors for 50 years, fits well with long standing lines of occupation to the North and West, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 2-1/2" dia. Iron Pipe/2-1/2" dia. Brass Cap stamped for corner location:

8" dia. Cedar	N27°E	27.26 feet	Scr. NBT
18" dia. Cedar (Existing)	S46°E	32.18 feet	Scr. NBT
9" dia. Cedar (Existing)	S30°W	25.11 feet	Scr. NBT
9" dia. Cedar	N51°W	57.7 feet	Scr. NBT
Metal Survey Sign Post	N75°E	13.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Aug. 8, 2000