

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**T Menominee**

(County)

Located In:

Corner Code *##*

1. Public Land Survey

T 34N R 28W

B3

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S 7 T \_\_\_\_\_ R \_\_\_\_\_

1

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

# 2 AMC

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

11

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Keith Sackett, in a field survey on August 7, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4	13	14	15	16	17	18							
5	19	20	21	22	23	24							
6	25	26	27	28	29	30							
7	31	32	33	34	35	36							
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

**B3**  
Quarter corner common to Sections 6 and 7. Original monument and accessories not found.

**# 1**  
One sixty-fourth corner west of center quarter corner of Section 7. Not set in original survey nor subsequently, apparently.

**# 2 MC**  
Meander corner on one sixty-fourth line west of N-S quarter line of Section 7. Not set in original survey nor subsequently, apparently.

**11**  
Meander corner on west one-sixteenth line of Section 7. Not set in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**B3**  
Corner restored midway and on line.

**# 1**  
Set midway and on line.

**# 2 MC**  
Set on the first N-S one sixty-fourth line west of the N-S quarter line on the left bank of the Menominee River.

**11**  
Set on the west one-sixteenth line on the left bank of the Menominee River.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**B3**  
Set 1" I.D. x 32" iron pipe with 4" aluminum cap.  
5" w. birch N31E 50.1', NBT  
4" w. birch S46E 38.9', NBT  
6" cedar S62W 56.3', NBT  
Wood post North 0.5'

**# 1**  
Set 1" I.D. x 32" iron pipe with 4" aluminum cap.  
7" aspen N33E 7.0', BT  
9" aspen S43E 10.25', BT  
5" w. pine S73W 14.1', BT  
9" w. pine N67W 26.95', BT

**# 2 MC**  
Set 1" I.D. x 32" iron pipe with 4" aluminum cap.  
15" basswood S02W 2.4', BT  
12" w. ash N56W 68.35', BT  
9" w. ash N13W 44.95', BT  
SE corner camp foundation N55E 34.6'

**11**  
Set 1" I.D. x 32" iron pipe with 4" aluminum cap.  
13" w. ash N33E 23.5', BT  
11" w. ash S57E 21.35', BT  
10" w. ash S32W 7.1', BT  
8" basswood N17W 21.75', BT

Signed by Keith Sackett

Date \_\_\_\_\_

Surveyor's Michigan License No. 19006

