

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located in:

Corner Code //

- 1. Public Land Survey T 34N R 28W C-3, C-4
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Paul Bressette, in a field survey on October 17, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numerical values and symbols for survey points.

A. Description of original monument and accessories and/or subsequent restoration:

- C-3 Corner common to Sections 5,6,7 and 8. Restored in 1955 by Billy Buckler RLS. Set 1" Iron pipe with 4" brass cap witnessed by a 6" soft maple N 81° W 45 lks and a 6" soft maple S 34° E 44 lks
C-4 Quarter Corner common to Sections 7 and 8. Restored in 1955 by Billy Buckler RLS. Set 1" Iron pipe with 4" brass cap witnessed by a 20" white pine S 58° E 68 lks and a 12" sugar maple N 08° E 38 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-3 Found monument and NW BT as described. No evidence remains of SE BT. Rewitnessed monument as found.
C-4 Found monument and NE BT as described. SE BT has been cut flush with ground. Rewitnessed monument as found.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

- C-4 1" Iron pipe w/ 4" brass cap
C-3 1" Iron pipe w/ 4" brass cap
18" Sugar maple N 11° E 25.25' (old NBT)
New NBT's
12" Hemlock S 26° E 23.5' (1/2 S, NBT)
12" Sugar maple S 46° W 32.7' (1/2 S, NBT)
5" White ash N 45° W 45.55' (1/2 S, NBT)
18" Soft maple N 78° W 29.8' (old NBT)
New NBT's
12" Red oak N 14° E 24.1' (S.5, NBT)
9" Soft maple S 38° E 52.45' (S.8, NBT)
8" Soft maple S 35° W 23.25' (S.7, NBT)

Signed by Paul R. Bressette

Date 11-6-91

Surveyor's Michigan License No. 37270

