

APR 06 1999

Approved \_\_\_\_\_ nee County  
 Land Sur \_\_\_\_\_ mentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 12/30, 1998  
Mike Davis RLS  
 Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>35N</u> R <u>28W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
 99 JAN -6 AM 8:54  
 PAGE # 706 BK 5  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE MI 49838

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

(SAME AS CORNER E-01, T34N - R28W.)

I, William Lenca, in a field survey on Sept. 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey - Township Boundary - by H. Brevoort, Jr. - B.T.'s - W. Pine, 14" - N75°E - 06 lks.; Hemlock, 10" - N46°W - 05 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1852: Original Survey - Sectional Subdivision - by Francis Coleman - B.T.'s - Hemlock, 18" - S58°E - 13 lks.; Hemlock, 8" - S35°W - 12 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1963: LCRC No. 416 (Vol. 3) by Billy D. Buckler states: 1/2" x 24" Iron bar buried in int. of rds N-S-E. TIES: PP - N44°E - 73 lks; 8" Elm - (NBT) - N61°E - 53-1/2 lks. No evidence of original corner.
- 1989: L.C.R.C. No. 857 by William Lenca states, "Found 1/2" dia. Iron Rod bent over - 24" below road surface. Reset corner from old witnesses." Set 5/8" x 24" Iron Rod / Ident. cap. TIES: Power Pole - N51°E - 48.17'; Balsam, 7" - S56°E - 64.58'; Balsam, 7" - S40°W - 47.07'; Anchor Pole - N28°W - 38.19'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner has been destroyed. We re-set the corner from information contained in Land Corner Recordation Certificate Number 857 by William Lenca, RLS No. 26461. The corner falls in the centerline of county roads North, South, and East. This location has been accepted and used by local surveyors for over 35 years and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum. cap stamped for corner location:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N51°E	47.28 feet	1' S. of Power Pole
8" dia. Balsam	S56°E	64.58 feet	Ex. B.T.
7" dia. Maple		38.35 feet	"X" in upper & lower
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N28°W	37.41 feet	1' E. of Anchor Pole
5/8" x 24" Iron Rod	West	33.00 feet	
Metal Survey Sign Post	West	33.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
 Surveyor's Michigan License No. 26461

Date Dec. 22, 1998

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

