

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Menominee

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>34</u> N. S., R. <u>29</u> E. W.	<u>M-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 26 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-3 N.E. Section corner - Section 12; Wood post - Tam. 10 - N28°W - 20 lks.; Tam. 10 - S24°W - 11 lks.; Tam. 8 - N50°E - 25 lks.; Tam 6 - S22°E - 29 lks; searched but nothing found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-3 Located N.W. corner of Sec. 12 and N.W. corner of Sec. 1 both with evidence of O.B.T.s Started at N.W. corner of Sec. 12 - mea. angle in N.E. quad. obtained by the difference in bearings recorded in the notes of original survey. Ran line east one mile to it's intersection with N-S Co. Rd. line is right in a section of old fence on the south side of a small field west of ¼ corner. Swamp call at 58.00 from the west fits well on or slightly south of our line but would not fit well if the line were moved north. Distances both north and south from the east end of our line fit reasonably well for swamp calls. We could move south 50 or 75 lks. and still be reasonable but not north. Set corner monument at the intersection of our random line and the centerline of the N-S Co. Rd. distance south to the E¼ corner of Sec. 12 fits well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 1" pipe, 4" aluminum cap; 7" Tamarack - S87°W - 34.45'; 6" Tamarack - N76°W - 39.25'; 8" Tamarack - N31°E - 31.30'; 8" Tamarack - S65°E - 21.85'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558