

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>34</u> N. S., R. <u>29</u> E. W.	<u>K-2, L-2, M-1</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 26, 1978 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
K-2 West $\frac{1}{4}$ corner - Section 1; wood post - w. pine 6 - N33°W - 9 lks.; aspen 14 - S35°E - 14 lks.; searched but nothing found.

L-2 Center $\frac{1}{4}$ corner - Section 1; not previously established.

M-1 N.E. Section corner; wood post - y. pine 36 - S51°W - 26 lks.; w. pine 36 - N23°E - 49 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
K-2 Set M.P.O.L. between the N.W. and S.W. corners of Section 1.

L-2 Set at intersection of E-W and N-S $\frac{1}{4}$ lines.

M-1 Set from remains (stp.) of 36" w.p. O.B.T. NE and red pine roots in road grade in place for S.W. O.B.T. swamp call west fits well with G.L.O. record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
ALL 1" pipe, 4" aluminum cap

K-2 8" oak - S72°W - 36.7'; 7" r. maple - N31°W - 10.4'; 15" oak - N48°E - 35.1'; 12" oak - S30°E - 4.45'

L-2 15" r. pine - S45°E - 45.1'; 12" r. pine - S56°W - 32.3'; 10" w. pine - N58°W - 56.8'; 14" r. pine - N73°E - 24.2'

M-1 D.N.R. Mon. buried in road; 12" oak - S66°W - 33.6'; 11" cedar - N61°W - 62.7'; 8" w. pine - N30°W - 51.1'; TW. 20" w. pine - N53°E - 57.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 9-7-78
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558