

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>34</u> N. S., R. <u>29</u> E. W.	<u>L-1, M-2</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 2 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- L-1 North  $\frac{1}{4}$  corner - Section 1; wood post - Tam. 3 - N45°W - 05 lks.; Tam. 3 - N75°E - 08 lks. Searched but nothing found.
  - M-2 East  $\frac{1}{4}$  corner - Section 1; wood post - y. pine 18 - N34°E - 04 lks.; spruce pine 10 - N21°W - 39 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-1 Set M.P.O.L. between the N.E. and N.W. section corners of Section 1.

- M-2 Set in line with old nearly obliterated fence line west and in centerline of N-S Co. Road. There is a newer fence west and a conc. post west of the road about 81' north of this position but it does not fit G.L.O. swamp calls and surrounding corners. I talked by telephone with the former owner of the S.E.  $\frac{1}{4}$  of Section 1, Mr. Ed. Reinus and he said he set the conc. post without knowledge of the true corner position. I, therefore disregarded it as evidence of the true corner position and accepted the position of the older fence which fits well.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- L-1 1" pipe, 4" aluminum cap and cedar stake; 7" cedar - S34°E - 57.6'; 6" cedar - S50°E - 65.2'; 10" tam. - S88°W - 98.5'; 6" cedar - N76°W - 95.4'
  - M-2 1" pipe, 4" aluminum cap; 6" r. pine - S70°W - 43.45'; 5" r. maple - N74°W - 70.45'; 9" w. pine - N41°E - 44.1'; 5" w. birch - S32°E - 50.6'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 9-7-78  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558