

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	T. <u>34</u> N. S., R. <u>29</u> E. W.	<u>5, 6, 9</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 20 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- 5 - N 1/16 corner on N-S 1/4 line of Section 1; not previously established.
  - 6 - N.E. 1/16 corner of Section 1; not previously established.
  - 9 - East 1/16 corner of Section 1; not previously established.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 5 - Set at proportionate position by closed traverse.
  - 6 - Set at computed center of the N.E. 1/4 of Sec. 1 by closed traverse.
  - 9 - Set M.P.O.L. between the E 1/4 corner and the center post of Section 1. Falls 105' south of existing E-W fence.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 5 - 1" pipe, 4" aluminum cap; R. maple 10" - N81°E - 5.65'; w. pine 20" - N15°E - 41.4'; b. ash 4" - N41°W - 25.9'; w. pine 18" - S79°W - 22.5'
  - 6 - 1" pipe, 4" aluminum cap; 8" w. birch - S40°W - 7.3'; 8" w. birch - N86°W - 6.7'; 15" oak - N1°E - 40.1'; 5" r. maple - S45°E - 11.2'
  - 9 - 1" pipe, 4" aluminum cap; 14" w. pine - S41°W - 30.05'; 16" w. pine - S8°W - 31.35'; 12" oak - N7°E - 2.3'; 14" oak - N55°E - 2.7'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558