

11

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Menominee (County), Located In, Corner Code. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and two dots in row 2, column J.

I, Paul Bressette, in a field survey on May 24, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- 1 West one-sixteenth corner common to Sections 35 and 2. Found 1" iron pipe 24.80' southerly of monumented position.
2 East one-sixteenth corner common to Sections 2 and 35. Not set in original survey. No evidence of subsequent establishment.
4 Northwest one-sixteenth corner of Section 2. Not set in original survey. No evidence of subsequent establishment.
8 West one-sixteenth corner of Section 2. Not set in original survey. No evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1 Corner position established mid-point and on-line between the Northwest and North Quarter Corners of Section 2. Found iron pipe was rejected as it is not on-line.
2 Corner position established mid-point and on-line between the Northeast and North Quarter corners of Section 2.
4 Corner position established at the intersection of the North and West one-sixteenth lines of Section 2.
8 Corner position established mid-point and on-line between the West and Center Quarter corners of Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 4 columns: 1 - DNR Monument, 2 - DNR Monument, 4 - DNR Monument, 8 - DNR Monument. Rows list monument types and measurements (e.g., 8" R.Maple N42°E 14.1').



Signed by Paul R. Bressette
Surveyor's Michigan License No. 37270

Date June 1, 1994