

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Table with columns: For corners in Menominee (County), Located In, Corner Code //
1. Public Land Survey T 34N. R 29W. J-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. Contains numbers 6-36 and a dot in cell J-2.

I, Paul Bressette, in a field survey on May 31, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
I-1 Quarter Corner common to Sections 2 and 35. 1848: H. Brevort, Jr. D.S., Set wood post witnessed by: Y. Pine 18 N55E 23 Lks.; W. Pine 30 N55W 53 Lks.
I-3 Quarter Corner common to Sections 2 and 11. 1852: Francis Coleman, D.S., set wood post witnessed by: Cedar 6 N53W 15 Lks; Cedar 6 S76E 15 Lks.
I-2 Quarter Corner common to Sections 2 and 3. 1852: Francis Coleman, D.S., set wood post witnessed by: Forked Black Oak 20 N56E 9 Lks; White Birch 6 S77W 18 Lks.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
-1 No evidence of original survey or restoration found. Corner position re-established mid-point and on-line between the Northeast and Northwest corners of Section 2.
I-3 No evidence of original survey or restoration found. Corner position re-established mid-point and on-line between the Southeast and Southwest corners of Section 2.
I-2 No evidence of original survey or restoration found. Corner position re-established mid-point and on-line between the Northwest and Southwest corners of Section 2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with columns: -1 DNR Monument, J-3 DNR Monument, I-2 DNR Monument
19" W.Pine N56E 1.05', 6" R.Oak S33E 21.65', 6" R. Oak S20W 19.1', 19" W.Pine N89W 5.6'
12" R.Maple N65E 41.45', Cedar Post SE 1.1', 4" R.Maple S43W 22.7', 10" R.Maple N66W 16.0'
8" R.Maple N24E 25.7', 5" R.Maple S31E 22.65', 10" R.Maple S05W 28.4', 6" R.Maple N33W 39.0'



Signed by Paul R. Bressette Date May 31, 1994

37270