

FEB 11 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Free County
Documentation
Act 345 Of
Validity
PA-014: 10/31/97
1997
McLAREN RLS

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey T34N R 27W C-11
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

97 NOV 21 PM 3:20
REGISTERED LAND SURVEYOR
MICHIGAN
546 BKS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Oct. 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 6" - N58.5°W - 11lks.; W. Pine, 9" - S48°E - 12 lks. All original evidence for this corner has been destroyed by logging activities.
- 1926: Plat of Wallace Summer Resort by A.L. Hillis states that a 1" x 15" iron rod encased in a 4" x 48" concrete cylinder.
- 1982: Certified Survey No. 317 by William Lenca, RLS No. 26461 indicates in the legend that a "Plat Monument" was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 4" square concrete monument with a 1" diameter iron rod in the center. This monument has been used by local surveyors for more than 70 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 4" square concrete monument with 1" dia. iron rod in center for corner position:

6" dia. Maple	N50°E	32.66 feet	Scr. NBT
7" dia. Maple	S59°E	15.73 feet	Scr. NBT
6" dia. Oak	S58°W	11.82 feet	Scr. NBT
6" dia. Oak	N52°W	6.71 feet	Scr. NBT
Metal Survey Sign Post	South	1.3 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 07, 1997



546