

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 346 Of
P.A. Of 1990 On 12/19, 1997
Mr. David P. S.
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

| For corners in MENOMINEE (County) | Located In: | Corner Code # |
|---|-----------------------------|---------------|
| 1. Public Land Survey | T <u>34</u> N R <u>27</u> W | C-12 |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| | T ___ R ___ | ___ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |
| | S ___ T ___ R ___ | ___ |

97 DEC 22 AM 11:26
REGISTERED FOR RECORD
576, BKS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Nov. 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Y. Pine, 15" - S42°E - 10 lks.; W. Pine, 8" - S89°W - 16 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1982: L.C.R.C. No. 549 by William Lenca, RLS 26461, states, "Found 1/2" Iron 16" below existing road surface in location indicated by existing occupation." Set 3/4" x 18" Iron Pipe/Identification cap over top of existing 1/2" Iron. TIES: W. Birch, 12" - N47°W - 55.25'; Oak, 6" - S58°E - 64.85'; Maple, 6" - S50°W - 84.09'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1/2 inch diameter iron pin in the centerline of a North - South County road. We verified that this was the same position used in L.C.R.C. No. 549 by measuring to 2 existing B.T.'s - 6" Oak - S58°E - 64.85 feet and 6" Maple - S50°W - 84.09 feet. This position matches closely with a proportional measurement between the NE Corner and the SE Corner of Section 31, has been used by local surveyors for many years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

| | | | |
|------------------------|-------|------------|----------|
| 8" dia. White Pine | N39°E | 41.85 feet | Scr. NBT |
| 10" dia. Oak | S56°E | 64.85 feet | Scr. NBT |
| 7" dia. Maple | S45°W | 78.71 feet | Scr. NBT |
| 12" dia. White Pine | N39°W | 89.13 feet | Scr. NBT |
| Metal Survey Sign Post | West | 34.1 feet | |



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 18, 1997
Surveyor's Michigan License No. 26461

576