

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located In: Corner Code -#

- | | | | | |
|------------------------------------|---|-------------|------------|------------|
| 1. Public Land Survey | T | <u>35NR</u> | <u>27W</u> | D-13 |
| | T | | R | |
| | T | <u>34N</u> | <u>27W</u> | <u>D-1</u> |
| | T | | R | |
| 2. Property Controlling in Section | S | | R | |
| | S | | R | |
| 3. Miscellaneous Property in Sec. | S | | R | |
| | S | | R | |

RECEIVED FOR RECORD
 95 DEC 27 PM 3:30
 PAGE # 279 BK 4
 BARBARA JOHNSON
 REGISTERED CLERK
 MENOMINEE, WISCONSIN 54958
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims
(SAME AS D-1 T34N-R27W)

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

William Lenca, in a field survey on May 5, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1847: Original Survey by Henry Floyd (Township Exterior) - B.T.'s - Cedar, 12" - N30°E - 33 lks (not evident); Elm, 12" - N35°W - 38 lks (not evident).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a field survey in May of 1995 we found a 1 inch diameter eye bolt in line with ancient fences North and East. The Center Quarter Corner of Section 32 has been monumented by Wisconsin Public Service. A straight line from this corner to the N1/4 Corner passes 0.39 feet East of the C1/4 Corner Monument. The distance from this corner East to the SE Corner of Section 32 is 2685.61 feet. The distance from this corner North to the C1/4 Corner Monument is 2656.42 feet. This corner position fits well with existing lines of occupation, has been accepted and used by local surveyors for many years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

6" dia. White Ash	N06°W	22.46 feet	Scr. NBT
5" dia. White Ash	S88°E	16.46 feet	Scr. NBT
14" dia. Maple	S03°E	64.22 feet	Scr. NBT
5" dia. White Ash	S85°W	30.87 feet	Scr. NBT
Survey Sign Post	S68°E	1.3 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 17, 1995
 Surveyor's Michigan License No. 26461

279