

REMONUMENTATION

FEB 11 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 10/31 1997
W. Lenca RLS
Chairman
97 NOV 21 PM 3:20
REGISTERED LAND SURVEYOR
STATE OF MICHIGAN
5477 BRS
Register of Deeds Stamp & File Number

For corners in

MENOMINEE
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>34N</u> R <u>27W</u> | <u>D-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Oct. 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Aspen, 14" - N80°E - 08lks.; W. Pine, 8" - S35°E - 11 lks. All original evidence for this corner has been destroyed by logging activities.
1980: An unrecorded survey by George B. Wilson, RLS No. 17607, prepared as a Certified Survey but never recorded, shows a subdivision of Fractional Section 29. In the legend of this survey, he describes the corner monument as an "HDR Berntsen Monument".
1983: Certified Survey No. 395 by William Lenca, RLS No. 26461, shows this corner as it relates to other corners in Section 29, and describes the corner monument as "HDR Bertsen Monument".


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3/4 inch x 5 foot Aluminum Rod with a 3-1/4 inch diameter Aluminum cap (known as a "HDR Bertsen Monument") at an ancient fence corner. Fences run north - south - east and west. The existing monument matches the description and record measurements shown in the above mentioned Certified Surveys, fits long standing lines of occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" x 5' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner:

6" dia. Maple	North	11.93 feet	Scr. NBT
14" dia. Maple	S68°E	19.76 feet	Scr. NBT
15" dia. Maple	S14°E	24.95 feet	Scr. NBT
9" dia. Maple	S69°W	24.61 feet	Scr. NBT
Metal Survey Sign Post	North	0.8 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 24, 1997