

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Reestablishment
Peer Group Under Act 325 Of
P.A. Of 1990 On 10/31, 1997
Mike Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE	Located In:	Corner Code #
(County)		
1. Public Land Survey	T34N R 27W	E-08
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

97 NOV 21 9 11 3 20
 REGISTERED LAND SURVEYOR
 WILLIAM LENCA
 No. 26461

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on June 18, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Y. Pine, 20" - S61°W - 54 lks.; Hemlock, 10" - S47°E - 22 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1978: Certified Survey No. 138 by George B. Wilson, RLS No. 17607, describes this corner as a 4" square concrete monument 36" long with 1/2" iron in the center and shows and shows ties to other corners including the C1/4 Corner.
- 1981: Recorded plat of "ROBERT'S SUBDIVISION" recorded by George B. Wilson, RLS No. 17607, shows a tie to this corner. The corner monument is not described.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The concrete monument described in Certified Survey No. 138 has been destroyed. We re-established its position by using Wilson's monument at the Center 1/4 of Section 21 and the existing right of way irons as shown on said survey. The position thus re-established fits with the tie to Robert's Subdivision. The corner falls in the centerline intersection of county roads running East - West and South, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N35°E	42.23 feet	
7" dia. Oak	S38°E	84.09 feet	Scr. NBT
20" dia. Oak	S55°W	72.67 feet	Scr. NBT
9" dia. White Pine	N35°W	52.54 feet	
Survey Sign Post	N35°E	43.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Oct. 07, 1997

