

# REMONUMENTATION

FEB 11 1998

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. of 1990 On 10/31 1997  
W.L. Davis RLS 16926  
Chairman

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	T34N R. 27W	E-09
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

97 NOV 21 PM 3:20  
PAGE # 549, BKS  
REGISTERED LAND SURVEYORS  
MICHIGAN STATE BOARD

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on June 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 10" - N75°W - 29 lks.; Maple, 10" - S64°E - 23 lks. All original evidence for this corner has been destroyed by logging activities.  
 1926: Plat of "BOROST SUMMER RESORT" by A.L. Hillis shows a tie to this corner and indicates a typical plat monument consisting of a 1" iron rod in 4" dia. concrete cylinder.  
 1980: An unrecorded survey by George B. Wilson, RLS No. 17607, prepared as a Certified Survey but never recorded, shows a subdivision of Fractional Section 29. In the legend of this survey, he describes the corner monument as an "HDR Berntsen Monument."  
 1981: Certified Survey No. 209 by William Lenca, RLS No. 26461 states "found stone at fence corner." Shows ties to other corners in Section 21.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 By using information from the above surveys, we determined the position of this corner and carefully searched the area. We were unable to recover any type of survey monument, however the position falls at an ancient fence corner. We dug down and recovered the point of the corner post, and is accepted as the best available evidence of the position of the original corner. Ancient fences run East - West and North from this location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 4' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner:

6" dia. Cherry	N27°E	7.94 feet	Scr. NBT
7" dia. Twin Cherry	S79°E	18.99 feet	Scr. NBT
8" dia. Cherry	N84°W	9.34 feet	Scr. NBT
9" dia. Cherry	N34°W	43.43 feet	Scr. NBT
Metal Survey Sign Post	South	1.6 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Oct. 07, 1997  
 Surveyor's Michigan License No. 26461

549