

APR 06 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Reconformation
Peer Group Under Act 345 Of

P.A. 061990 On 10/29 1998
James S. Wainio P.S.
Chairman

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 34NR 27W F-01

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

(SAME AS CORNER F-13, T35N - R27W)

I, William Lenca, in a field survey on June 09, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd - B.T.'s - W. Pine, 30" - N70°E - 40 lks.; W. Pine, 14" - N30°W - 30 lks. All original evidence for this corner has been destroyed by county road improvements.
Terrain Call: Enter swamp 3 Chains West and 2.5 Chains East of Corner.
- 1976: Certified Survey Number 59 by George B. Wilson shows a 1" round steel pin at this corner location.
- 1977: L.C.R.C. Number 160 by George B. Wilson states, "Found Long Iron Spike. Re-set 1-1/4" Iron Bar, 2 feet south of Road Centerline. Nothing near for direct ties. Should pick up strong on audio meter."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1-1/4" diameter iron rod 30 inches long in a location as indicated in Land Corner Recordation Certificate Number 160 by George B. Wilson, RLS No. 17607. The corner falls in line with the county road centerline running South and 2 feet south of the East - West centerline. This location has been used in many surveys, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" N35°E 33.06 feet 1' S. of 10" Spruce
- 9" dia. Cedar S50°E 83.85 feet Scr. NBT
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" S51°W 26.45 feet 1' N. of PP
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" N38°W 91.63 feet 1' SE of 26" W. Pine
- Metal Survey Sign Post N05°E 33.4 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 21, 1998

RECEIVED FOR RECORD
98 NOV 16 AM 10:00
PAGE # 646 BKS
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		5		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

