

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Fear Group Under Act 345 Of
P.A. Of 1990 On 10/31 1997
McDRAVIS RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located in:	Corner Code #
<u>MENOMINEE</u> (County)		
1. Public Land Survey	<u>T4N R 27W</u>	<u>F-05</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED LAND SURVEYOR
WILLIAM LENCA
No. 26461
07 NOV 21 PM 3:20
555 BK5

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Lenca, in a field survey on June 09, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1-12 above were in conformance with regulations and rules therefore as required in the current manual of survey. Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Y. Pine, 12" - S37°E - 11 lks.; Y. Pine, 6" - N77°E - 12 lks. All original evidence for this corner has been destroyed by logging activities.
- 1901: Plat of Survey in Section 9 T34N-R27W by Albert Hass, County Surveyor, states "set 4" cedar post from Government B.T."
- 1974: L.C.R.C. No. 86 by George B. Wilson states he dug a hole 10' square (shaving the earth with a shovel) and found the mark of a 4" square cedar post. Set 2" dia. aluminum pipe with cap stamped Land Survey Corner RLS 17607. 4" x 4" cedar post 7' long set adjacent. TIES: Oak, 7" - N83°W - 24.6'; Oak, 7" - N44°E - 64.3'; Oak, 6" - N55°W - 14.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered George Wilson's 2-1/2" iron pipe with 3-1/4" aluminum cap next to a 4" square wood post and channel iron. Since this corner was placed in the location of the cedar post set by Albert Hass from an original B.T., we accepted the corner as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 2-1/2" dia. Iron Pipe/3-1/4" dia. Alum. cap stamped for corner location:

16" dia. Oak	N45°E	64.67 feet	Scr. NBT
12" dia. Oak	S75°E	48.77 feet	Scr. NBT
7" dia. Oak	S26°W	15.86 feet	Scr. NBT
11" dia. Oak	N63°W	14.94 feet	Scr. NBT
Metal Survey Sign Post	North	1.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 09, 1997

555