

# SURVEY & REMONUMENTATION

JUN 23 1994

COMMISSION

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

P.A. Of 1990 On 5/18/94 199 94

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Mac Davis  
Chairman

For corners in  
MENOMINEE

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34N</u> R <u>27W</u>	F-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
94 MAY 20 PM 3:31  
PAGE # 69 BK. 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, William Lenca, in a field survey on March 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 8", N06°W, 13 lks & Hemlock, 6", N49°E, 23 lks. All original evidence for this corner location has been destroyed by county road improvements.
- 1981: LCRC No. 300 recorded by George B. Wilson, RLS No. 17607, states that a 1/2" dia. iron rod was set on line with a fence line to the North and South, and in the centerline of a gravel road. B.T.'s - 8" Ash, S64°W, 57.4' & 5" Maple, S16°E, 45.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A 1/2" diameter Iron Pin was found in the centerline of an East-West county road in line with an old fence line running South from this location. This position fits with the recorded distance (as shown in LCRC 300) to the SE Corner of Section 33, T34N-R27W, and is accepted as the best available evidence for the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Sct Berntsen 5/8" x 24" Iron Rod/3-1/4" dia. cap stamped for corner:

12" dia. W. Ash	Scr. NBT	N24°E	50.49 feet
18" dia. W. Ash	" "	S30°E	57.52 feet
6" dia. W. Ash	" "	S28°W	81.13 feet
6" dia. W. Ash	" "	N54°W	68.74 feet
Survey Sign Post		North	33 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date April 22, 1994  
Surveyor's Michigan License No. 26461