

APR 06 1999

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

P.A. of 1990 On 10/29, 1998  
William J. Lenca P.S.  
Chairman

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34NR</u> R <u>27W</u>	<u>G-01</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD  
8 NOV 16 AM 10:00  
Chairman  
PAGE # 642 BK# 5  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MI 49859  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

(SAME AS CORNER G-13, T35N - R27W)

I, William Lenca, in a field survey on May 20, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1						○						
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey - Township Boundary - by H. Floyd - B.T.'s - W. Pine, 24" - N50°E - 21 lks.; W. Pine, 10" - N48°W - 35 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1848: Original Survey - Sectional Subdivision - by James H. Mullett - B.T.'s - W. Pine, 14" - S13°W - 14 lks.; W. Pine, 8" - S55°E - 26 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1976: Certified Survey Number 59 by George B. Wilson shows this corner as being a 1" round steel pin.
- 1977: L.C.R.C. Number 161 by George B. Wilson states, "Found old iron pin, Re-set 1" dia. iron x 40" long. This pin will pick up strong on audio meter. Nothing near for ties. This Corner directly tied into Certified Survey in the NE 1/4 of said Section 4."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1" diameter iron rod 36 inches long as described in Land Corner Recordation Certificate Number 161 by George B. Wilson, RLS No. 17607. Existing iron is 2 feet North of the centerline of an East - West county road and in line with the centerline of county roads running North and South. This corner has been consistently used by local surveyors for many years, fits existing occupation, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N38°E	38.50 feet	1' E. of P.P.
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S45°E	47.11 feet	@ Sign Post
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S45°W	42.51 feet	1' W. of Rd. Sign
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N46°W	53.00 feet	1' N. of Tel. Box
Metal Survey Sign Post	S45°E	47.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 21, 1998

