

REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/31 1997
W. Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located In:

Corner Code #

- | | | | |
|---------------------------------------|-------|--------------------|-------------|
| 1. Public Land Survey | | <u>T34N R. 27W</u> | <u>G-06</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling
in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous
Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

REGISTERED FOR RECORD
 97 NOV 21 PM 3:20
 BUREAU 557 BKS
 SAUCARIA JOHNSON
 REGISTER OF DEEDS
 COUNTY OF MENOMINEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on June 19, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		5		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16	15	14		13			
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Y. Pine, 20" - S14°W - 26 lks.; Y. Pine, 18" - S40°E - 15 lks. All original evidence for this corner has been destroyed by county road improvements.
 1978: Certified Survey No. 56 by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in the NW1/4 of Section 15. The corner monument is described as "found a wood stake - set pin".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 5/8 inch diameter iron pin along side of a 2 foot long wood post in the centerline intersection of county roads running North - South - East. This corner fits with record distances as shown in Certified Survey No. 56, and with long standing lines of occupation, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

20" dia. White Pine	N67°E	75.11 feet	Scr. NBT
12" dia. White Pine	S44°E	79.17 feet	Scr. NBT
10" dia. White Pine	S43°W	77.62 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N84°W	31.51 feet	1' N. of P.P.
Metal Survey Sign Post	N84°W	32.4 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by W. Lenca
 Surveyor's Michigan License No. 26461

Date Oct. 13, 1997