

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/18, 199 2
Mike Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In:	Corner Code #
T <u>34N</u> R <u>27W</u>	<u>G-10</u>
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

RECORDED 118-11-26
97 DEC 22 AM 11:26
581, BKS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on July 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	19		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Tamarack, 10" - N40°E - 30lks.; Tamarack, 10" - N55°E - 34 lks. All original evidence for this corner has been destroyed by logging activities.
- 1980: L.C.R.C. No. 253 by George B. Wilson, RLS 17607, says Old wood stake, Mr. Glen Gunderson said he knows has been in place for 50 years, since he lived on the land for a period of over 52 years. Re-set with 4" square concrete monument. Nothing near for ties. Back of L.C.R.C. shows partial Section Subdivision of Section 28.
- 1980: Certified Survey No. 201 by George B. Wilson, RLS 17607, shows this corner as it relates to other corners in the SE 1/4 of Section 28. The corner monument is described as "Con. Mon."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 4 inch square concrete monument in position matching record measurements to other corners in Section 28 as shown in a sketch on the back of L.C.R.C. No. 253. This corner position has been accepted and used for 70 years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3-1/4" dia. Alum. cap stamped for corner location on existing monument:

7" dia. Maple	N46°E	62.06 feet	Scr. NBT
6" dia. Maple	S02°E	29.26 feet	Scr. NBT
Metal Survey Sign Post	South	0.9 feet	

Nothing Else Nearby

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 13, 1997

581