

# SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 10/31 199 7  
McLain RGS  
Chairman

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION For corners in  
MENOMINEE  
(County)

Located In:	Corner Code #
T34N R 27W	G-12
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

REGISTER OF DEEDS  
MENOMINEE COUNTY  
NOV 21 PM 3:21  
559 BK5

Register of Deeds Stamp & File Number

- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on July 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Tamarack, 6" - S89°E - 17 lks.; Tamarack, 10" - S21°W - 07 lks. All original evidence for this corner has been destroyed by logging activities.
- 1991: L.C.R.C. No. 911 by William Lenca, RLS No. 26461, states "set 3/4" x 60" Alum. rod / 3-1/2" cap marked "Menominee County Survey Marker" on line and midway between section corners. This position fits well with G.L.O. terrain call to swamp edge North." TIES: Carsonite - N16°E - 1.64'; W. Ash, 9" - S35°E - 3.53'; W. Ash, 6" - S41°W - 18.10'; W. Ash, 9" - West - 21.60'; W. Ash, 8" - N45°W - 20.00'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 3/4 inch x 5 foot Aluminum rod with a 3-1/4" diameter Aluminum cap stamped for corner. We also found 4 existing B.T.'s and carsonite in place as described in L.C.R.C. No. 911 (sect part A). This corner is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Accepted existing 3/4" x 5' long aluminum rod/3-1/4" dia. Alum. cap stamped for corner:

Carsonite Marker	N16°E	1.64 feet	
9" dia. White Ash	S35°E	3.53 feet	Scr. NBT
6" dia. White Ash	S41°W	18.10 feet	Scr. NBT
9" dia. White Ash	West	21.60 feet	Scr. NBT
8" dia. White Ash	N45°W	20.00 feet	Scr. NBT

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 24, 1997



559