

REMONUMENTATION

SECTION
FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of

P.A. Of 1990 On 10/31 199 7

Mike Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T4N R 27W</u>	<u>H-09</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

97 NOV 21 PM 3:21
REGISTERED LAND SURVEYOR
WILLIAM LENCA
No. 26461

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William Lenca, in a field survey on July 22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Y. Pine, 18" - S05°E - 21 lks.; W. Pine, 18" - N43°W - 16 lks. All original evidence for this corner has been destroyed by logging activities.
- 1900: Plat of Survey by Albert Hass, County Surveyor, shows a partial subdivision of Section 22 and states "sect 4" cedar post from Gov't B.T."
- 1977: L.C.R.C. No. 172 by George B. Wilson, RLS No. 17607, states "sectional subdivision by Albert Hass - I used his measurements which checks well with a fence running to the north and to the west." Set 4" square concrete monument 30" long / 1/2" dia. pin in center. NBT's: Douglas Fir, 6" - North - 28.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The concrete monument described in L.C.R.C. NO. 172 was destroyed when the county road commission excavated a large sand hill where the corner stood. We found a Norway Pine B.T. (described as 6" Douglas Fir in C.S. No. 172) still standing on the edge of the sand cut. We established the center 1/4 corner, the SW Corner and the SE Corner of Section 22, and using measurements as shown in C.S. No. 172, we established the position for the S1/4 Corner (H-9). The position thus established falls in the bottom of the sand cut, fits with the existing B.T. and falls in line with an ancient fence running North, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

9" dia. Norway Pine	N67°E	89.55 feet	Scr. NBT
8" dia. Norway Pine	S28°E	114.02 feet	Scr. NBT
9" dia. White Pine	S26°W	65.44 feet	Scr. NBT
6" dia. Norway Pine	N46°W	38.13 feet	Scr. NBT
Metal Survey Sign Post	North	1.0 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with an EDM. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 24, 1997

560