

REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/13 199 7
McAnis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34</u> N R <u>27</u> W	I-08
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
97 DEC 22 11:27
584 BKS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Nov. 03, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - W. Pine, 18° - N18°W - 20 lks.; W. Pine, 10° - S60°E - 08 lks. All original evidence for this corner has been destroyed by railroad construction and by county road improvements.
- 1900: Survey by Albert Hass states "Set "T" rail 3' long which is 39 lks west of the west rail of the C&NW RR Co's Track.
- 1977: L.C.R.C. No. 169 by George B. Wilson states, "Found old iron pin, checks well with survey by Albert Hass in the year 1900." 1/2" dia. iron pin - 28.38' west of the centerline of the rails - tied into certified survey No. 75.
- 1993: Certified Survey No. 794 by William Lenca, RLS 26461, shows this corner as being 2604.43' south of the N.E. Corner of Section 22, T34N - R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a P.K. nail set over a very old 1/2 inch diameter iron in location as described in L.C.R.C. No. 169. Corner falls 2' north of present county road centerline and 26.0' west of the west rail of the present Chicago and Northwestern Railroad. This fits very closely with Albert Hass's record measurement of 39 links (25.74 feet). This position has been used by local surveyors for many years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:
- | | | |
|--|-------|------------|
| Southwest Bolt on base of Railroad Signal | N68°E | 44.14 feet |
| Southwest Bolt on base of Railroad Signal | S39°E | 25.25 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 2' N. of Power Pole | S45°W | 36.49 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 2.2' N. of C.R. Sign | N58°W | 42.71 feet |
| Metal Survey Sign Post | N14°W | 36.0 feet |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Nov. 04, 1997
Surveyor's Michigan License No. 26461

584