

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Forer Group Under Act 345 Of
P.A. of 1990 On 12/18 1997
McSAVIN 265
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located In:	Corner Code #
T ^{34N} R ^{27W}	I-12
T R	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

RECEIVED FOR RECORD
97 DEC 22 AM 11:27
PAGE 588, BK 5
GEOGRAPHIC INFORMATION SYSTEMS

Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, William Lenca, in a field survey on June 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 15" - S80°E - 28 lks.; Hemlock, 15" - N53°W - 25 lks. All original evidence for this corner has been destroyed by U.S. 41 Highway improvements.
- 1980: L.C.R.C. No. 256 by George B. Wilson set 1/2" iron pin by single proportionate measurement. Corner falls 8.5' east of the edge of U.S. 41 pavement.
- 1982 Certified Survey No. 304 by George B. Wilson shows this corner in relation to other corners in Section 35, T34N - R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1/2 inch iron pin on the east shoulder of U.S. 41 as indicated in L.C.R.C. No. 256 by G.B. Wilson. This corner fits well with a single proportional location, and is accepted as a careful and faithful reestablishment of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

6" dia. Oak	N44°E	137.81 feet	Scr. NBT
7" dia. Cedar	S58°E	88.77 feet	Scr. NBT
6" dia. Tamarack	S59°W	120.65 feet	Scr. NBT
10" dia. Maple	N48°W	99.02 feet	Scr. NBT
Metal Survey Sign Post	N77°E	51.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with an EDM. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 27, 1997