

# SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. of 1990 On 12/18, 1997  
William Lenca  
 Chairman

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in  
MENOMINEE  
 (County)

Located In:	Corner Code #
T <u>34N</u> R <u>27W</u>	<u>J-07</u>
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

REGISTERED FOR RECORD  
 97 DEC 22 AM 11:27  
 \$91.35  
 REGISTERED FOR RECORD  
 Register of Deeds Stamp & File Number

- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on July 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 6" - N82°W - 13 lks.; Y. Pine, 12" - S26°E - 10 lks. All original evidence for this corner has been destroyed by county road improvements.
  - 1981: L.C.R.C. No. 310 by William Lenca states "found iron in line with c/l Co. Rd. N & in line with occupation S. & 6.8' S of c/l Co. Rd. E - W. This pos. checks closely with extending line & doubling dist. of Plat Monuments found in Sup. Plat of Wallace No. 1 & 2" - TIES: Spruce, 12" - S49°E - 20.8' (Gonc); Power pole - N54°W - 59.48' (Fd.); W. Birch, 7" - N60°E - 103.05' (Fd.).

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- We recovered a 1/2 inch diameter iron 6 inches below the road surface and in line with a county road centerline to the north. The iron is 8' +/- south of a newly resurfaced east - west county road centerline. This iron has been used by local surveyors for many years, matches well with established lines of occupation, and is accepted as the best available evidence of the position of the original corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- |                                                                                            |       |             |                 |
|--------------------------------------------------------------------------------------------|-------|-------------|-----------------|
| Scr 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box: |       |             |                 |
| 10" dia. Balsam (Not blazed)                                                               | N11°E | 115.60 feet |                 |
| N.W. Corner of Residence                                                                   | S32°E | 55.78 feet  |                 |
| 6" dia. Cedar                                                                              | S60°W | 44.29 feet  | Scr. NBT        |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"                              | N50°W | 61.43 feet  | 1.6' W. of P.P. |
| Metal Survey Sign Post                                                                     | South | 18.9 feet   |                 |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Oct. 31, 1997  
 Surveyor's Michigan License No. 26461