

REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/19 1997
Mike Davis PLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
(County)

Located in:	Corner Code #
T-34N R-27W	J-09
T- R-	
T- R-	
T- R-	
S- T- R-	
S- T- R-	
S- T- R-	
S- T- R-	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

RECORDED FOR SECTION
PAGE # 592 BK 5
97 DEC 22 AM 11:27
MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS

Register of Deeds Stamp & File Number

- Lot No. _____, Recorded Plat _____
- Private Claims _____

I, William Lenca, in a field survey on May 13, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Elm, 12" - S84°W - 75 lks.; Alder, 4" - N35°W - 35 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: L.C.R.C. No. 309 by William Lenca states "set a railroad spike in centerline of E - W Co. Rd. and in line with fence south. This position fits with GLO Terrain Calls to the E. and W. and with existing 1/16 fence east." TIES: Chiseled "+" in west end of north headwall - N52°E - 29.65'; Chiseled "+" in west end of south headwall - S55°E - 31.5'; Power pole - S69°W - 94.90'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a railroad spike in the centerline of a county road east - west and in line with an old fence south and 3 Witnesses as described in L.C.R.C. No. 309. This position has been accepted and used by local surveyors for at least 16 years, fits well with existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" at W. end of N. Wing Wall	N49°E	29.84 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" at W. end of S. Wing Wall	S49°E	31.21 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" Survey Sign Post	South	28.31 feet
	South	29.3 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26441

Date Oct. 31, 1997