

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
 Land Survey Reestablishment
 Four Group Under Act 345 of
 P.A. of 1990 On 12/30 1997
McL. Davis RLS

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located In: Corner Code #

1. Public Land Survey

T 34N R 27W K-06

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED FOR RECORD
 97 DEC 30 PM 4:06
 PAGE # 630 BKS
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE COUNTY, WISCONSIN

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on Dec. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		10	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Fir, 8" - S11°W - 19 lks.; Fir, 8" - S25°E - 20 lks. All original evidence for this corner has been destroyed by logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We computed the single proportional location for this corner, traversed in to it and searched the area. We found no evidence of the original corner accessories, or evidence of subsequent restoration. We set this corner midpoint and on a line between the Northwest Corner and Southwest Corner of Section 13, T34N - R27W. This location fits well with a GLO call to a stream 1.5 chains North, and is accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

10" dia. White Ash	N08°E	28.05 feet	Scr. NBT
11" dia. Elm	N89°E	32.05 feet	Scr. NBT
4" dia. White Ash	S09°E	37.27 feet	Scr. NBT
11" dia. White Ash	S75°W	31.22 feet	Scr. NBT
Metal Survey Sign Post	North	1.0 feet	
Little Lindberg Creek	North	118 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.



Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Dec. 18, 1997

630