

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/18 199 2
Mc Davis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION 26 Corners in
MENOMINEE
(County)

Located In:	Corner Code #
T <u>34</u> N R <u>27</u> W	K-10
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

97 DEC 22 AM 11:28
REGISTERED LAND SURVEYOR
599 DK5
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Mar. 04, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				4			3			2	1
3													
4	7	8				9			10			11	12
5													
6	10	17				16			15			14	13
7													
8	19	20				21			22			23	24
9													
10	30	29				28			27			26	25
11													
12	31	32				33			34			35	36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 10" - S60°W - 24 lks.; Cedar, 10" - S65°E - 08 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1980: Certified Survey No. 198 by George B. Wilson, RLS No. 17607, shows this corner in relation to other corners in Section 26, T34N - R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1/2 inch diameter Iron Pin in the centerline of a county road North and South, and in line with ancient fence lines East and West. This corner has been used continuously by local surveyors for at least 17 years, fits existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location:
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" East 28.37 feet
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 1.1' S. of 10" wood Gate Post S66°W 55.80 feet
- 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 1.1' N. of Power Pole N31°W 50.91 feet
- Metal Survey Sign Post East 30.3 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 03, 1997
Surveyor's Michigan License No. 26461

599