

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
 Land Survey Remonumentation
 Four Group Under Act 246 Of
 P.A. Of 1989 On 12/30, 1997
Ma. Davis RLS
 Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE

(County)

Located In: Corner Code #

1. Public Land Survey

T 34N R 27W L-05

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

REGISTERED FOR RECORD
 97 DEC 30 PM 4:07
 PAGE # 631, 285
 BARBARA MORRISON
 REGISTER OF DEEDS
 MENOMINEE MI 49858

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, William Lenca, in a field survey on Dec. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 8" - S36°W - 23 lks.; Hemlock, 12" - N05°W - 12 lks. All original evidence for this corner has been destroyed by county road improvements.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a Railroad Spike in the centerline of an East - West county road. This corner was set by doubling the distance from the Northwest Corner of Section 13 to an existing fence line along the West 1/16 line of Section 13. This position matches well with the centerlines of M-3 Lane to the North and an old lane to the South, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod 3/16" dia. Alum. cap stamped for corner location in Monument Box:

7" dia. White Ash	N21°E	39.82 feet	Scr. NBT
10" dia. Elm	N67°E	58.72 feet	Scr. NBT
5/8" x 24" Iron Rod 1/2" dia. Alum. cap marked "WITNESS MARKER"	S40°W	40.42 feet	1.0' W. of P.P.
5/8" x 24" Iron Rod 1/2" dia. Alum. cap marked "WITNESS MARKER"	N25°W	33.54 feet	@ Sign Post
Metal Survey Sign Post	N25°W	34.5 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
 Surveyor's Michigan License No. 26461

Date Dec. 18, 1997

