

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/13 1997
Mr. Davis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
MENOMINEE
(County)

Located In:	T <u>34</u> N R <u>27</u> W	Corner Code #	L-07
	T___ R___		_____
	T___ R___		_____
	T___ R___		_____
2. Property Controlling in Section	S___ T___ R___		_____
	S___ T___ R___		_____
3. Miscellaneous Property in Sec.	S___ T___ R___		_____
	S___ T___ R___		_____

REGISTERED FOR RECORD
97 DEC 22 AM 11:28
BOOK # 601 P. 5
MICHIGAN REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on July 23, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Becch, 10" - N73°E - 12 lks.; Becch, 6" - S31°E - 10 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1989: Certified Survey No. 625 by William Lenca, RLS No. 26461, shows this corner as it relates to other corners in Section 13, T34N-R27W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a P.K. nail in the centerline of county roads East - West - North and in line with an ancient fence line running South. This P.K. Nail matches with measurements to corners to the 1/16 Corner and the Section Corner to the West as shown in Certified Survey No. 625. This position has been used by local surveyors for several years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 1.5' E. of Road Sign	N32°E	45.25 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 1.0' N. of Sign Post	S02°W	30.96 feet
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" 1.5' W. of Power Pole	N27°W	52.14 feet
Metal Survey Sign Post	S02°W	32.0 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 05, 1997