

SURVEY & REMONUMENTATION

FEB 11 1998

Michigan Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/13 199 2
McAnis Pcs
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
MENOMINEE
(County)

Located In:	Corner Code #																								
<table border="0"> <tr><td>P</td><td>R</td><td>27W</td></tr> <tr><td>T</td><td>R</td><td></td></tr> <tr><td>T</td><td>R</td><td></td></tr> <tr><td>T</td><td>R</td><td></td></tr> <tr><td>S</td><td>T</td><td>R</td></tr> <tr><td>S</td><td>T</td><td>R</td></tr> <tr><td>S</td><td>T</td><td>R</td></tr> <tr><td>S</td><td>T</td><td>R</td></tr> </table>	P	R	27W	T	R		T	R		T	R		S	T	R	S	T	R	S	T	R	S	T	R	L-11
P	R	27W																							
T	R																								
T	R																								
T	R																								
S	T	R																							
S	T	R																							
S	T	R																							
S	T	R																							

REGISTERED FOR RECORD
97 DEC 22 AM 11:28
INDEX # 603, BKS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, William Lenca, in a field survey on May 12, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 10" - N0.5°W - 14 lks.; Hemlock, 12" - S01°E - 04 lks. All original evidence for this corner has been destroyed by county road improvements.
 - 1981: L.C.R.C. No. 295 by William Lenca states, "Set corner in line with old fence line to the North and in center of existing County Road. This position fits well with occupation to the East and with GLO Land Tie to the West." Set 3/4" x 18" Iron Pipe in centerline of County Road. TIES: W.Pine, 12" - N17°W - 37.24'; Balsam, 6" - N53°E - 44.98'; Power Pole (Tack) - S74°E - 134.80'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
We found a 3/4" x 18" Iron Pipe in the centerline of an East - West County Road and in line with an old fence to the North as described in L.C.R.C. No. 295. This position has been used by local surveyors for at least 16 years, matches existing lines of occupation, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

6" dia. Cedar	N43°E	43.46 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	South	33.69 feet	
6" dia. White Ash	N60°W	65.85 feet	Scr. NBT
14" dia. White Pine	N17°W	37.24 feet	Scr. NBT
Metal Survey Sign Post	South	34.2 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Dec. 05, 1997
Surveyor's Michigan License No. 26461

603