

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 845 Of
P.A. Of 1990 On 12/18 1997
Alvin Davis PLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in
MENOMINEE
(County)

Located In: Corner Code #

1. Public Land Survey

T 34N R 27W M-05
T 34N R 26W A-05
T N R W

2. Property Controlling
in Section

S T R
S T R
S T R
S T R

3. Miscellaneous
Property in Sec.

606 BKS
97 DEC 22 AM 11:29
REGISTERED FOR STAMP
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____
SAME AS CORNER A-5, T34N-R26W

I, William Lenca, in a field survey on July 02, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey - Township Boundary by H. Floyd - B.T.'s - Sugar, 14" - N30°W - 34 lks.; Hemlock, 12" - S20°W - 30 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1848: Original Survey - Sectional Subdivision by James H. Mullett - B.T.'s - Elm, 12" - N57°E - 53 lks.; Hemlock, 10" - S65°E - 17 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1981: L.C.R.C. No. 322 by William Lenca states, "Found a large spike in a position indicated by the intersection of county road centerlines north, south, east, and west." Set 1/2" x 18" Iron/Ident. cap R.L.S. 26461. TIES: Tel. Cable Box marked with "+" on top - N40°W - 36.82'; Concrete Project Marker with "+" on top - S41°W - 43.28'; Power Pole with tack in side - S35°E - 44.86'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1/2 inch diameter iron in the centerline of a four way county road intersection as indicated in L.C.R.C. No. 322. This corner position fits well with other corners in the area and with long standing lines of occupation, has been used by local surveyors for many years, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

28" dia. Maple	N45°E	80.53 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S32°E	45.77 feet	1.0' S. of P.P.
8" dia. Tamarack	S50°W	80.37 feet	Scr. NET
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N35°W	37.30 feet	0.7' S. of Fence Cor.
Metal Survey Sign Post	S32°E	46.6 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Dec. 09, 1997