

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35. NR. 25 W.

Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 9, 10, 15, 16.

DESCRIPTION OF CORNER MONUMENT Placed 1/2" x 3" Steel bar in center of E & W road.

WITNESSES TO CORNER 6" Soft Maple S 56° W 47 1/2 links

8" Aspen S 53° E 59 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by Double Proportionate Measurement from corners in all four directions.

No evidence of original B.T.'s.

Set a wood post 15 links South of Section Corners.

Scribed = S.

C.

10'

N.

Corner placed and witnessed July 11, 1956.

SURVEYORS SEAL

SIGNED

Billy L. Buckler
REGISTERED LAND SURVEYOR

DATE 7/17/56