

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35. NR. 25 W.

Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 8, 9, 16, 17

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 8" Cedar S 52° W 27 links

8" Cedar S 51° E 45 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by double Proportionate Measure to corners in all four directions.

Swamp edge to West checks.

No evidence of original B.T.'s.

Corner placed and witnessed July 12, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 7/17/56
REGISTERED LAND SURVEYOR