

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35. NR. 25 W. .

Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 16, 17, 20, 21 .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 5" W. Ash N 60° W 12½ links

5" W. Ash N 62° E 11 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Established Section Corner.

Swamp edges North and East check very good.

Distance checks to Section Corner one mile West and Proportionate Measure N. and S. ok.

Hemlock stp. (badly rotted) and possible Cedar stp. bottom in proper place.

Corner placed and witnessed May 21, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 5/23/56
REGISTERED LAND SURVEYOR