

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 35. NR. 25. W. . .

Menominee COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 17, 18, 19, 20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 34" White Pine Stp. N 72° W 34 links

24" White Pine Stp. N 74° E 52½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Corner from two probable Hemlock stp. bottoms in proper position.

Traces of two stakes in soil. Distance checks to swp. and stream West; and to swp. and stream South.

Corner lies 1.88 chs. W. and 1.33 chs. S. of 80.00 ch. marker from North.

Corner placed and witnessed April 19, 1956.

SURVEYORS SEAL

SIGNED *Billy D. Bucher*  
REGISTERED LAND SURVEYOR

DATE 5/14/56