

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 35 N.R. 25 W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{4}{3}$ 9/10

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 4/24/68, F. J. Bray

WITNESSES TO CORNER..... 12" cedar stump (NBT) S 78° E, 26½ links



6" cedar stump (NBT) N 25° E, 15 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between corners 1/2 mile to north and east and 1 mile to south and west. No original evidence found.

SURVEYOR'S SEAL

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR

DATE

5/28/68

Frank J. Bray