

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Menominee COUNTY


T 35 N R's 25 & 26W

DESCRIPTION OF CORNER Section corner for sections T35N 25/30 T35N
R26W 36/31 R25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5/26/70, F. J. Bray

WITNESSES TO CORNER..... 4" B. Spruce (S.25) (NBT) N 28° W, 5.5'



4" B. Spruce (S.36) (NBT) S 12° W, 9.6'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by placing on line and the single proportioned measurement between town corner to south and section corner to north.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J. Bray

DATE 6/25/70

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68