

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES  
LAND CORNER RECORD

Menominee COUNTY


T 35 N R 25 W

DESCRIPTION OF CORNER Section corner for sections <sup>28/27</sup> 33/34

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 6/12/70, F. J. Bray with B. McDonald

WITNESSES TO CORNER..... 6" Aspen (S.28) (NBT) N 56° W, 15.7



6" Aspen (S. 27) (NBT) N 45° E, 15.0

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners one mile to south, east, and west and 1/4 corner 1/2 mile to north. Cedar stump with axe mark near. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED Frank J. Bray DATE 6/29/70  
REGISTERED LAND SURVEYOR  
Frank J. Bray

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68